VIBE 6030

60" x 30" x 19"

Vibe is a new collection of therapeutic bathtubs with minimalist and contemporary flair. The collection is perfect for urban city dwellers who want to bring value and refinement to smaller bathrooms.



DESCRIPTION	тми	TUB
Drop-in	BVIBRD00T-XX	BVIBRD00N-XX
Alcove - Left	BVIBRB0LT-XX	BVIBRB0LN-XX
Alcove – Right	BVIBRBORT-XX	BVIBRBORN-XX
Slim deck	BVIBRD10T-XX	BVIBRD10N-XX
Slim deck – Left	BVIBRB1LT-XX	BVIBRB1LN-XX
Slim deck – Right	BVIBRB1RT-XX	BVIBRB1RN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
Geysair®	Included
Illuzio Chromatherapy BCHRO6	\$

TUB Soaker	\$
Illuzio Chromatherapy BCHRO6	\$
WarmTouchShell® BWTS	\$
DOT control	Included with therapy

FEATURES					
Installation type		Drop-in, Undermount & Alcove (3 walls)			
No. of bath	ners	*	Imp. gallons		36
US gallons		44	Integrated tile flange Includ		Included
INTEGRATED WASTE & OVERFLOW BOVERINI-XX					
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10		Installed & Included			
STANDARD COLOR					
White 01	Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
COLOR		
Gray 05	\$	
FINISH		
UltraVelour Matte Finish (White only) BVEL	\$	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX		
Black Chrome 12, Matte Black 19, Satin Brass 18	\$	
SKIRT MULTIFIT 1 1/2" (standard deck only) BSMUL-XX		
White 01, Biscuit 02	\$	
Gray 05	\$	
CONTROL (TMU only)		
MiaMulti® BMIAM2-XX	\$	
IF REQUIRED BY CONSTRUCTION CODE OR INSTALLED WITH ITD		
Brass waste & overflow kit BDRCOB	\$	
Brass waste kit BDRCB	\$	

Don't forget that an integrated tile flange is available at no extra cost. You must specify drain position (right or left).


Turbine must be remotely installed in certain conditions. With the control on the deck, a complete shower door cannot be installed. Don't forget to specify the finish of the integrated waste & overflow.


TOTAL PRICE





VIBE 6030





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 7/8"
В	Outside edge to centre of overflow	2 1/2"
С	Total length	60"
D	Total width	30"
E	Bathing well length	44"
F	Bathing well width	19 1/8"
G	Deck width	1 7/8"
Н	Deck width at waste end	2"
ı	Height from bottom of TUB to top deck	18 1/2"
J	Height from drain to center of overflow	14 1/2"
K	Slope of backrest	27°
L	Height from bottom of lip to top std deck	1 1/2"
М	Height from bottom of lip to top slim deck	1/2"
N	Tile flange height	1"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell[®] position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water	Should be 70% of water capacity of TUB or greater.	Cutting to	
supply required	, , ,	Approx. sl	
Turbine	Access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 hz , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 hz , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.		
			Other
Our products mus	st be installed by certified professionals only and according to our Owner's Manual as well as federal,	Controls-l	
on products must be mistained by certained professionals only and according to our owners winding as well as lederal, provincial/state and local building codes and regulations (www bainulars com/documentation/documentation)		Bath & tur	

Cutting template	# 90000078			
Approx. shipping weight	200 lbs			
Turbine power	550 W			
Air heater	600 W			
WARRANTY				
Controls-LED-Geysair*	5 years			
Bath & turbine*	20 years			
4 C				

^{*} Some restrictions apply | www.bainultra.com/warranty





The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.